



തൃശ്ശൂർ മുനിസിപ്പാലിറ്റി
മലയാളസർവ്വകലാശാല
 വാക്കട്, മലപ്പുറം - 676 502
 ഫോൺ :0494 2631230

നം:2510/2026/ഇ3/അഡ്മിൻ

തീയതി : 05.09.2026

കാട്ടേഷൻ നോട്ടീസ്

തൃശ്ശൂർ മുനിസിപ്പാലിറ്റി മലയാളസർവ്വകലാശാലയുടെ രംഗശാലയ്ക്കു പിറകുവശത്തെ മഴവെള്ളപ്പാത്തി മാറ്റി സ്ഥാപിക്കുന്ന പ്രവൃത്തി ഏറ്റെടുത്ത് നടത്തുന്നതിന് കാട്ടേഷൻ ക്ഷണിക്കുന്നു.

തൃശ്ശൂർ മുനിസിപ്പാലിറ്റി മലയാളസർവ്വകലാശാലയുടെ അക്കാഡമിക് ബ്ലോക്കിലെ രംഗശാലയ്ക്കു പിറകുവശത്തെ ചോർച്ച ഒഴിവാക്കുന്നതിന് മഴവെള്ളപ്പാത്തി മാറ്റി സ്ഥാപിക്കുന്ന പ്രവൃത്തി നിർവ്വഹിക്കുന്നതിന് യോഗ്യതയുള്ള അംഗീകൃത സ്ഥാപനങ്ങളിൽ നിന്നും വ്യക്തികളിൽ നിന്നും മുൻപെച്ച കാട്ടേഷനുകൾ ക്ഷണിച്ചുകൊള്ളുന്നു.

പ്രവൃത്തിയുടെ വിശദാംശങ്ങൾ ചുവടെ ചേർക്കുന്നു.

Sl No	Description	Quantity
1	50.18.9.19.2 Dismantling PVC pipes with clamps/clips at 1.00 m spacing ,includes removing one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 110 m dia 4 Kgf/cm2 - External work - labour charge.	22.000 metre
2	50.18.9.18.1 Dismantling PVC pipes with clamps/clips at 1.00 m spacing ,includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge - Exposed on wall 75 mm dia 6Kgf/cm2 - labour charge.	16.000 metre
3	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	22.000 sqm
4	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates,bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	138.600 kg
5	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	32.000 sqm
6	15.31 Dismantling tiled roofing. complete including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	18.700 sqm
7	Steel work for purlin/single section with G I pipes including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	73.200 kg
8	17.4 Providing and fixing 250mm uPVC square gutter pipe over GI clamp of same profile @ 0.5 c/c etc complete. as per direction of Engineer -in-charge .	40.000 metre

9	Providing and fixing 250mm uPVC square gutter pipe compact runner etc complete. as per direction of Engineer -in-charge .	6.000 no
10	Providing and fixing 250mm uPVC square gutter pipe stop end etc complete. as per direction of Engineer -in-charge .	6.000 no
11	Providing and fixing cone chain with S hooks with 10meter length complete. as per direction of Engineer -in-charge	18.000 no
12	Providing and fixing PVC pipes including fixing the pipe with clamps/ clips/ at 1.00 m spacing . This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 110 mm dia 6 Kgf/cm2 - External work- Exposed on wall	20.000 metre
13	Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 110 mm dia Elbow	12.000 no
14	Providing and fixing PVC moulded fittings / accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 110 mm dia 45 degree Elbow	4.000 no
15	Providing & fixing departmental roof pressed clay tile (Mangalore tile) of 20 mm nominal thickness and of approved size and as per approved pattern on steel frame work complete (steel frame work to be paid separately)	9.350 sqm
16	Providing & and fixing on roof pressed clay tile (Mangalore tile) of 20 mm nominal thickness and of approved size and as per approved pattern on steel frame work complete (steel frame work to be paid separately)	9.350 sqm

1. ഓരോ ഇനത്തിന്റെയും നിരക്കുകൾ രേഖപ്പെടുത്തി ക്വട്ടേഷൻ സമർപ്പിക്കേണ്ടതാണ്.
2. കവറിന്റെ പുറത്ത് "രംഗശാലക്കു പിറകുവശത്തെ മഴവെള്ളപ്പാത്തി മാറ്റി സ്ഥാപിക്കുന്ന പ്രവൃത്തിക്കുള്ള ക്വട്ടേഷൻ " എന്ന് രേഖപ്പെടുത്തിയിരിക്കണം.
3. ക്വട്ടേഷൻ 16/09/2026 ഉച്ചക്ക് 2 മണിക്ക് മുൻപായി സർവകലാശാല ഓഫീസിൽ ലഭിച്ചിരിക്കണം.
4. ഹാജരുള്ള ദർഘാസ്കാരുടെ/അധികാരപ്പെടുത്തിയ പ്രതിനിധികളുടെ സാന്നിധ്യത്തിൽ അന്ന് തന്നെ വൈകിട്ട് 3.00 മണിക്ക് രജിസ്ട്രാറോ അല്ലെങ്കിൽ രജിസ്ട്രാർ ചുമതലപ്പെടുത്തിയ ഉദ്യോഗസ്ഥനോ ക്വട്ടേഷനുകൾ തുറക്കുന്നതായിരിക്കും.
5. ക്വട്ടേഷൻ അംഗീകരിക്കുന്നതിനും, നിരസിക്കുന്നതിനുമുള്ള അധികാരം സർവകലാശാലയിൽ നിക്ഷിപ്തമായിരിക്കും.
6. കരാർ ലഭിക്കുകയാണെങ്കിൽ വർക്ക് ഓർഡർ ലഭിച്ച് 30 ദിവസത്തിനകം പ്രവൃത്തി പൂർത്തീകരിക്കേണ്ടതാണ്.

കൂടുതൽ വിവരങ്ങൾക്ക് ഓഫീസിൽ നേരിട്ടോ 0494 - 2631230/240 എന്ന നമ്പറിലോ, www.malayalamuniversity.edu.in എന്ന വെബ്സൈറ്റിലോ ബന്ധപ്പെട്ടാൽ ലഭിക്കുന്നതാണ്.

(ഒപ്പ്/-)
ഡോ.കെ.എം.ഭരതൻ
രജിസ്ട്രാർ ഇൻ ചാർജ്

പകർപ്പ് :

വി.സി.കാര്യാലയം/ഫിനാൻസ് വിഭാഗം/പി.എ.ടു.രജിസ്ട്രാർ/
യൂണിവേഴ്സിറ്റി എഞ്ചിനീയർ/ഐ.ക്യു.എ.സി/ഓഫീസ് നോട്ടീസ് ബോർഡ്/
വെബ്സൈറ്റ്/തിരുർ മുനിസിപ്പാലിറ്റി ഓഫീസ്/വെട്ടം ഗ്രാമപഞ്ചായത്ത്/
നിറമരുതുർ പഞ്ചായത്ത് ഓഫീസ്/ഓഫീസ് രേഖ/കരുതൽ രേഖ